# **Bid Addendum Report**

## Fikkal Rural Municipality, Sindhuli

Fikkal Rural Municipality, Sindhuli Fikkal, Sindhuli Dudhouli, Sindhuli Nepal

Addendum No: 3

Published On: 16-04-2020 13:00

Invitation No: FRM/Sindhuli/Works/NCB/02/076-077

Dated On: 24-02-2020 10:00

#### Following changes are made in the bid document

## **Chapter: General Information**

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	2020-04-09 17:00:00	2020-04-16 13:00:00
2	Bid Submission DeadLine	2020-04-19 12:00:00	2020-04-30 12:00:00
3	Bid Opening Date	2020-04-19 13:00:00	2020-04-30 13:00:00

## **Chapter: Bill of Quantities**

1 Pı	1 Provisional Sum							
	Procument Item Details							
SL. No	Item Description			Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Insurance for the loss of damage materials, equipment, proporties death and 3rd parties as per cont	onal injury o	r PS	1	150000	150000		
2	Provisional sum for the investiga as directed by the Employer / Pr in Specification / Special Provis	oject Ma			1	150000	150000	
2 C	onstruction work							
2.1	Works for complete or part constr	uction ar	nd civil engin	eering work				
2.1.1	Building construction work							
2.1.1	.1 Civil Works							
Procument Item Details								
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's	Rate (in words)	Total Amount(NPR)	
1	Information Board (board Iron sheet 18 SWG L=4'00" B=3'00" , border black iron pipe 0.5"*0. 5" & stand black iron pipe 1.5" Ø H=6'00", Stand) all complete as per specifications and instructions of project manager.	Nos	1.0					
2	Site preparation work, of contractor office ,Labour camp, temporary toilet, counsultant office, site protection,baricating with net & saftey all complete with cleaning and disposal of debrises, uprooting roots, solid wastes etc. all complete.	LS	1.0					
3	Earthwork in excavation for foundation in hard soil upto the required depth and disposal of excavated materials upto 50m lead and 1.50m lift including dressing of sides, ramming the bottom as per drawing, specification and approval of site engineer	Cum	675.07					
4	Dry stone soling in foundation and floor including sand filling in joints, leveling, watering etc. as per standard specification & Engineer's Instruction all complete.	Cum	44.48					
5	Providiing, laying, compacting and curing plain M10 1:3:6 cement concrete in foundation and super structure with cement, sand and stone ballast 20mm down finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer, all complete.	Cum	29.68					

	Procument Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)	
6	Providing, laying, compacting and curing M20 1:1.5:3 plain cement concrete for column, slab, beams, tie beam, Lintel, Sill and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimesions all complete as per specifications, drawings and instructions of the site engineer, all complete.	Cum	437.74				
7	Form work where it is provided as seperate item using steel props and 19mm water proof plyboard as material. It includes all labour, materials & other incidental required for the construction and romoval of forms as described in the specification. It further covers the forming work that is required for properly supporting the member until the construction.	Sqm	1505.07				
8	Torsteel/TMT steel bars (Grade 415/500) reinforcement work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for foundation. column, beam, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands of steel bars.	Kgs	68725.18				