

# **Bid Addendum Report**

## **Fikkal Rural Municipality, Sindhuli**

Fikkal Rural Municipality, Sindhuli  
Fikkal, Sindhuli  
Dudhouli, Sindhuli  
Nepal

**Addendum No: 1**

**Published On: 09-04-2020 17:00**

**Invitation No: FRM/Sindhuli/Works/NCB/03/076-77**

**Dated On: 17-03-2020 00:00**

## Following changes are made in the bid document

### Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-04-09 17:00:00
2	Bid Submission DeadLine	2020-04-16 12:00:00	2020-04-19 12:00:00
3	Bid Opening Date	2020-04-16 13:00:00	2020-04-19 13:00:00
4	Authorised Representatives Address	Fikkal, Sindhuli Sindhuli Dudhouli	Fikkal, Sindhuli Sindhuli

## Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Insurance for the loss of damage to works, plant, materials, equipment, properties and personal injury or death and 3rd parties as per contract data.	PS	1	120000	120000	
2	Provisional sum for the investigations / laboratory tests as directed by the Employer / Project Manager as stated in Specification / Special Provisions	PS	1	100000	100000	
2 Construction work						
2.1 Works for complete or part construction and civil engineering work						
2.1.1 Building construction work						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earthwork excavation in foundation of all types of soil including dewatering, shoring and strutting, preparing the bed for foundation as per specification and as directed by A/E.	Cum	21.6			
2	Earth fill work and tempering with sprinkle of water as per specification and directed by A/E	Cum	91.22			
3	Bolder Soling work with tempering in required level as per specification and directed by A/E	Cum	17.28			
4	Providing and Laying plain cement concrete(PCC) of M15 (1:2 4) Grade with 20mm and down size graded stone aggregate as leveling course in floor foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	Cum	10.32			
5	Providing and Laying plain cement concrete(PCC) of M20 (1:1.5: 3) Grade with 20mm and down size graded stone aggregate as leveling course in floor foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	Cum	78.87			

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
6	Providing and fixing in position TMT Thermex Reinforcement Bar (Fe500) of various diameters for all RCC work, at any elevation as per detailed design and drawings including de rusting, straightening, cutting, bending, hooking and tying in position with 18 SWG soft annealed wire at each junction as per design and detail for all type of RCC elements	KG	11143.99			
7	Brick masonry (Local made first class) with Reinforced concrete bands to be provided at sill, lintel and roof level up to the super structure from foundation in cement sand mortar (1:4) including scaffolding, curing as per specification and as directed by A/E.	Cum	39.6			
8	12 mm thick Cement Sand Plaster(1:4) on wall as per specification and as directed by A/E	Sqm	543.44			
9	Screeding(1:2:4) Work 75mm thick as per specification and as directed by A/E	Sqm	103.18			
10	3mm cement sand punning(1:1) as per specification and as directed by A/E	Sqm	103.18			
11	Sal wood work for door and window Frame	Cum	1.45			
12	Random Rubble stone masonry work with cement sand mortar 1:4 with curing for sub structure and also for retaining wall as per specification and directed by A/E	Cum	20.4			
13	Providing and fixing smooth surface wooden form work with required material as per specification and directed by A/E	Sqm	664.34			
14	Two coat weatrercoat painting work for outer surface of building as per specification	Sqm	152.93			
15	Two coat Distemper painting work for inner surface of building as per specification	Sqm	421.87			
16	38 mm thick Sal wood pannaled shutter works	Sqm	19.18			
17	4 mm glazed shutter works with 38 mm thick Sal wood frame	Sqm	23.42			