

Bid Addendum Report

Fikkal Rural Municipality, Sindhuli

Fikkal Rural Municipality, Sindhuli
Fikkal, Sindhuli
Dudhouli, Sindhuli
Nepal

Addendum No: 1

Published On: 16-04-2020 12:00

Invitation No: FRM/Sindhuli/Works/NCB/04/076-77

Dated On: 18-03-2020 00:00

Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-04-16 12:00:00
2	Bid Submission DeadLine	2020-04-17 12:00:00	2020-04-30 12:00:00
3	Bid Opening Date	2020-04-17 13:00:00	2020-04-30 13:00:00

Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Insurance for the loss of damage to works, plant, materials, equipment, properties and personal injury or death and 3rd parties as per contract data.	PS	1	50000	50000	
2	Provisional sum for the investigations / laboratory tests as directed by the Employer / Project Manager as stated in Specification / Special Provisions	PS	1	50000	50000	
2 Construction work						
2.1 Works for complete or part construction and civil engineering work						
2.1.1 Building construction work						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earthwork excavation in foundation of all types of soil including dewatering, shoring and strutting, preparing the bed for foundation as per specification and as directed by A/E.	Cum	129.09			
2	Earth fill work and tempering with sprinkle of water as per specification and directed by A/E	Cum	82.59			
3	Bolder Soling work with tempering in required level as per specification and directed by A/E	Cum	28.74			
4	Providing and Laying plain cement concrete of M10(1:3:6) Grade with 20mm and down size graded stone aggregate as leveling course in foundations including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	Cum	3.09			
5	Providing and Laying plain cement concrete(PCC) of M15 (1:2 4) Grade with 20mm and down size graded stone aggregate as leveling course in floor foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	Cum	10.32			

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
6	Providing and Laying plain cement concrete(PCC) of M20 (1:1.5: 3) Grade with 20mm and down size graded stone aggregate as leveling course in floor foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	Cum	100.05			
7	Providing and fixing in position TMT Thermex Reinforcement Bar (Fe500) of various diameters for all RCC work, at any elevation as per detailed design and drawings including de rusting, straightening, cutting, bending, hooking and tying in position with 18 SWG soft annealed wire at each junction as per design and detail for all type of RCC elements	KG	13351.79			
8	Brick masonry (Local made first class) with Reinforced concrete bands to be provided at sill, lintel and roof level up to the super structure from foundation in cement sand mortar (1:4) including scaffolding, curing as per specification and as directed by A/E.	Cum	53.23			
9	Random Rubble stone masonry work with cement sand mortar 1:4 with curing for sub structure and also for retaining wall as per specification and directed by A/E	Cum	5.62			
10	Providing and fixing smooth surface wooden form work with required material as per specification and directed by A/E	Sqm	626.85			