

Bid Addendum Report

Fikkal Rural Municipality, Sindhuli

Fikkal Rural Municipality, Sindhuli
Fikkal, Sindhuli
Dudhouli, Sindhuli
Nepal

Addendum No: 1

Published On: 16-04-2020 12:00

Invitation No: FRM/Sindhuli/Works/NCB/05/076-77

Dated On: 19-03-2020 10:00

Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-04-16 12:00:00
2	Bid Submission DeadLine	2020-04-19 12:00:00	2020-04-30 12:00:00
3	Bid Opening Date	2020-04-19 13:00:00	2020-04-30 13:00:00
4	Authorised Representatives Address	Fikkal, Sindhuli Sindhuli Dudhouli	Fikkal, Sindhuli Sindhuli

Chapter: Bill of Quantities

1 Provisional Sum							
Procument Item Details							
SL. No	Item Description			Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Insurance for the loss of damage to works, plant, materials, equipment, proporties and personal injury or death and 3rd parties as per contract data.			PS	1	50000	50000
2	Provisional sum for the investigations / laboratory tests as directed by the Employer / Project Manager as stated in Specification / Special Provisions			PS	1	15000	15000
2 Construction work							
2.1 Road Construction Work							
Procument Item Details							
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)	
1	Earthwork excavation in road all tupes of soil including dewatering, shoring and strutting, preparing the bed for foundation as per specification and as directed by A/E.	M3	151.12				
2	Stone Soling work with tempering in required level as per specification and directed by A/E	M3	170.5				
3	Providing and Laying plain cement concrete(PCC) of M10 (1:3 6) Grade with leveling course in foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	M3	63.94				
4	Providing and Laying plain cement concrete(PCC) of M20 (1:1.5 3) Grade with leveling course in foundation including tamping, curing etc. complete for all depths and heights as per specification and as directed by A/E	M3	124.0				
5	Providing and fixing in position TMT Thermex Reinforcement Bar (Fe500) of various diameters for all RCC work, at any elevation as per detailed design and drawings including de rusting, straightening, cutting, bending, hooking and tying in position with 18 SWG soft annealed wire at each junction as per design and detail for all tvpe of RCC elements	KG	4900.48				

Procument Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
6	Random Rubble stone masonry work with cement sand mortar 1:6 with curing for sub structure and also for retaining wall as per specification and directed by A/E	M3	55.8			