Ref No: RELIEFNEPAL/RFQ/FY024/025-004

REQUEST FOR QUOTATION (RFQ)



Date of RFQ issued: 1-Dec-2024

Relief Nepal, Sindhuli is planning to procure below mentioned goods so invites quotations from interested suppliers for the same. The detailed specification conditions are as follows:

Item No.	Items Name	Specifications	Unit	Quantity	Rate	Total Amount with VAT
Α	Site A: Laying of Gab	ion wall in Shree Ma Vi Ratamata School, kholagaun, Phikkal-3				
1	Hoarding Board	Supplying and Installation Of GI sheet hoarding Board with iron pole Specifying Brief Description of Project in specified size, shape and other details all complete.	nos	1.00		
2	Digging for foundation	Earthwork in excavation of foundation upto 0.6m depth for gabion boxes using labour: all complete work as per the instruction of site engineer (including disposal up to 10m lead and 1.5m lift.)	cum	22.50		
3	Soling work	Dry stone soling, levelling work for foundation for gabion boxes all complete work as directed by site engineer	cum	0.75		
4	Gabion work	Supplying,fabricating, Laying of gabion boxes (Heavy),hexagonal mesh size 100mmx120mm;Box size (3x1x1)m in three layers including stone packing (16sqm) all complete work as per instruction of site engineer	nos	30.00		
5	Backfilling	Back filling using 0.63cum excavator for better appearance all complete work as per instruction of site engineer	cum	90.00		
					Subtotal 1	

Item No.	Items Name	Specifications	Unit	Quantity	Rate	Total Amount with VAT
В	Site B:Construction	of Drinking Water Supply System in Shree Sunkoshi Secondary S	chool, Kha	ngsang, Phikl	kal-4	
1	Hoarding Board	Supplying and Installation Of GI sheet hoarding Board with iron pole Specifying Brief Description of Project in specified size, shape and other details all complete.	nos	1.00		
	Intake of size					
2	Site clerance	Site clerance by cutting tree, bushes and removing roots all complete works as per instruction of site engineer	sq.m	12.00		
1 7 1	Earthwork for foundation	Earthwork excavation for foundation in an hard Soil by Labours all complete works as directed by Site Engineer	cum	0.90		
4	Soling work	Dry Stone soling levelling work for foundation of Rubble Stone all complete works as directed by site engineer	cum	0.11		
5	PCC works	PCC works in 1:3:6 c/m all complete work as directed by site engineer	cum	0.11		
1 6 1	Stone masonary work	Stone Masonary works in 1:6 c/m without scaffoling as directed by site engineer	cum	0.75		
7	Plaster work	12.5 mm thick cement plaster in 1:3 c/m as directed by site engineer	sq.m	3.75		
8	Punning work	3 mm thick cement punning works in 1:1 c/m as directed by site engineer	sq.m	3.86		
	Pipes					
9	HDPE pipes	Providing, Supplying, laying and jointing 10 PN HDPE pipe and fittings for drinking water supply of 2" dia pipe in intake(63mm) upto 100m,1 1/2" dia pipe(50mm) upto 400m and 1" dia pipe(32mm) upto 1600m all complete work as per instruction of site engineer	Rm	2100.00		
					Subtotal 2	

Item No.	Items Name	Specifications	Unit	Quantity	Rate	Total Amount with VAT
С	Site C:Laying of Gab	ion wall in Shree Barabise Basic School, Thuldhunga, Phikkal-5				
1	Hoarding Board	Supplying and Installation Of GI sheet hoarding Board with iron pole Specifying Brief Description of Project in specified size, shape and other details all complete.	nos	1.00		
2	Site clearance	Excavation of earthwork using 0.63cum excavator for site clerance all complete work as per instruction of site engineer	cum	202.50		
3	Digging for foundation	Earthwork in excavation of foundation Manually including disposal up to 10m lead and 1.5m lift as directed by site engineer	cum	22.50		
4	Soling work	Dry stone soling, levelling work for foundation for gabion boxes all complete work as directed by site engineer	cum	0.75		
5	Gabion work	Supplying,fabricating of gabion boxes (Heavy),hexagonal mesh size 100mmx120mm;Box size (3x1x1)m in three layers including stone packing (16sqm) all complete work as per intstruction of site engineer	nos	30.00		
6	Backfilling	Back filling upto the road level using 0.63cum excavator as directed by site engineer	cum	24.30		
					Subtotal 3	•

Item No.	Items Name	Specifications	Unit	Quantity	Rate	Total Amount with VAT
D	Site D:Construction of	f well in Shree Basic School, Tinkhande, Phikkal-6				
1	Hoading Board	Supplying and Installation Of GI sheet hoarding Board with iron pole Specifying Brief Description of Project in specified size, shape and other details all complete.	nos	1.00		
2	Earthwork	Earthwork in excavation for foundation of Well all complete as directed by site engineer	cum	49.83		
3	RCC rings	Providing, supplying, Laying and jointing 4' RCC rings with 1:2 mortar for all the rings upto 10 meter depth as mentioned above; all complete works as per instruction of site engineer	Rm	12.00		
4	Electric motor pump	Supply and Fixing/fitting of 1.0 H P Electric motor pump (Submersible) Italian or equivalent; with required wires, cables, switches, sockets, all acceeries and tools; all complete works as per instruction of site engineer	nos	1.00		
5	Soling work	Dry stone soling, levelling work for foundation of rubble stone all complete work as per instruction of site engineer	cum	0.83		
6	PCC with punning work	50 mm thick flooring works with 1:2:4 PCC with punning work all complete as directed by site engineer	sq.m	5.56		
					Subtotal 4	
					Grand Total	

Total amount in Words:

Item No.	Items Name	Specifications	Unit	Quantity	Rate	Total Amount with VAT
Note:- All the works should be completed in the specified time within the quoted rate.						
	Rate of each items are inclusive of VAT					

Terms and Conditions:

- Quotation should be submitted by 7 December 2024, by 5:00 pm in sealed envelope. Quotations received after the specified date and time of the invitation w considered. The RFQ should have official stamp and signature.
- 2 Quoted rate should be inclusive of VAT,Transportation and other necessary Taxes (if applicable). Applicable Taxes will be deducted at source as per Govern Rules & Regulations.
- The goods/works should be delivered as per the Relief Nepal's instruction. In case of delay in delivery, 2% penalty will be charged on a weekly basis which the time of payment.
- Relief Nepal reserves the right to reject any or all quotation. The contract will be awarded as per Relief Nepal's bid evaluation criteria and the successful bidc notified at the earliest date possible.
- Payment to be made within 30 days after received of goods and undisputable invoice, if you have any objection or expectation please mention. Payment will payee cheque or online Bank Transfer in favor of your Company.
- 6 This rate agreement will be valid for one year.
- 7 Please put the item rate including all the costs associated with the materials, labors, transporattion and overhead.
- Interested companies are required to submit the copy of PAN/VAT registration document ,company registration document, latest tax clearance c with quotation form.

Tel: 047-520915

Email: afo@reliefnepal.org.np

If the above Terms and Conditions are acceptable to you, please submit your competitive proposals.

Sent by:
Signature:
Contact Person: Dik Kumari Budhathoki
Designation: Admin & Finance Officer

Contact Number: 047-520915 Organization: Relief Nepal, Sindhuli



ions, terms and

Remarks		

Remarks

Remarks	

Remarks	
	_

Remarks

vill not be

nment of Nepal

will deducted at

der(s) will be

be made via A/C

ertificate along